



NOTES:

1. APRON SHALL BE CONSTRUCTED A MINIMUM OF 18 FEET FROM THE EDGE OF ROAD.
2. PAVEMENT SECTION TO BE 7 INCHES THICK NON-REINFORCED CONCRETE MDOT SHA MIX NO. 9 OR 1.5 INCHES HOT MIX SUPERPAVE 9.5 MM FOR SURFACE (PG 64S-22, LEVEL 1), 3.0 INCHES HOT MIX SUPERPAVE 19.0 MM FOR BASE (PG 64S-22, LEVEL 1), AND 6.0 INCHES GRADED AGGREGATE BASE (GAB).
3. PIPE MATERIAL SHALL BE CLASS IV REINFORCED CONCRETE OR HDPE PIPE.
4. MINIMUM PIPE SIZE IS 15" AND MINIMUM LENGTH IS 30'.
5. MINIMUM COVER FROM TOP OF PIPE TO TOP OF SUB-BASE:
 - 0.75' FOR CONCRETE PIPE (TOP OF SUB-BASE IS BOTTOM OF AGGREGATE BASE)
 - 1.0' FOR HDPE PIPE (DURING CONSTRUCTION, MAINTAIN A MINIMUM 2' TEMPORARY COVER)

CARROLL COUNTY, MARYLAND DEPARTMENT OF PLANNING AND LAND MANAGEMENT	USE IN COMMON DRIVEWAY APRON WITH CULVERT	PLATE NO.
		UIC 8
ISSUED:	REVISED:	
REVISED:	REVISED:	